ascolite®
A Better Solution

TECHNICAL DATASHEET

ASCOREPAIR CRM

Economic, High Strength Concrete Repair Mortar



INDEX

RECOMMENDED APPLICATION	02
TECHNICAL DATA	02
PRODUCT KEY FEATURES	02
APPLICATION METHODS	03
SURFACE PREPARATION	03
PRIMING	03
COVERAGE	03
MIXING	03
APPLICATION	03
CURING	04
PACKAGING	04

PRODUCT INTRODUCTION

ASCOREPAIR CRM is a high strength, shrinkage compensated concrete repair mortar. ASCOREPAIR CRM is a fine-grained one component mortar to smooth out concrete and reinforced concrete, to fill cracks/voids and repair damaged substrates. The range of application is from 5mm to 50mm. ASCOREPAIR CRM provides strong adhesion with many substrates and may be applied both on vertical and horizontal surfaces inside and outside the buildings. It can be mixed with ASCOBOND 450 to improve the adhesion and flexibility.

ascolite®
A Better Solution

KEY FEATURES

1. High build repairs achievable in a single application
2. Low shrinkage
3. Reinforced with glass fibers
4. Waterproof
5. High compressive strength
6. For external & internal use
7. Excellent adhesion with many substrates
8. Internal or external applications
9. Easy to use- simply add water and mix

RECOMMENDED APPLICATIONS

1. Repair of concrete damaged by reinforcement corrosion or damage
2. Repairs to spelled columns, beams, slab etc. caused by corrosion of steel
3. High build repairs for vertical, overhead and horizontal repairs
4. Waterproof render to concrete, brickwork and block work
5. Repairs of edges, cracks and holes etc.

TECHNICAL PROPERTIES

Appearance	Non-metallic grey powder
Workability Time	20 ± 5 minutes
Fresh wet density	2000 ± 50 kg/m^3
Compressive Strength	≥ 15 N/mm^2 @ 7 days ≥ 30 N/mm^2 @ 28 days
Flexural Strength	≥ 3 N/mm^2 @ 28 days
Pullout Bond strength	≥ 2 N/mm^2 @ 28 days
Water Demand	16 ± 2 %
Full Cure Time	28 Days

APPLICATION METHODS:

1. Surface Preparation

Substrates should be clean and free from all contaminants, loose particles, coatings, dirt, mould, oil etc. Substrates must be sound, rough and dampened to ensure a good bond. Prior to placing grout, surface should be saturated for a minimum period of four hours and preferably for twenty-four hours. Pre-wet the substrate so that it is slightly moist. Expose the grains close to the surface.

2. Mixing

Pour water into a clean container and add dry mortar ASCOREPAIR CRM. Mix thoroughly with a mixer for approximately 3 minutes until homogeneous. Allow to mature for approximately 1 minute. Then mix again for at least 1 minute until the proper consistency for working has been achieved.

3. Conditions for Use

i. Temperature of the material, air and substrate: from minimum + 5 °C to maximum + 35 °C
ii. Low temperatures increases, while the high temperatures decreases the working and setting time.

4. Application Method

Any cracked or weakened surface should be removed and repaired to provide a solid foundation. It is recommended that for large areas a minimum depth of 5 mm be prepared as to avoid excessive feather edging or skim coating. Break out the repair area to a minimum of 5 mm up to the saw cut edge. Scabbing or high pressure water blasting should be used to remove laitance and provide a mechanical key. If any corroded steel is present remove all loose scale and corrosion/rust deposits. Grit blasting is effective in removing corrosion, and all steel including re-bars should be cleaned to a bright condition. Immediately after cleaning steel, the steel should be treated with ASCOPRIME RUSTCON. This will stop further oxidation and corrosion. For excellent bonding to the substrate ASCOBOND 450 should be mixed with OPC at the mixing ratio 1:1.

Apply the mixed ASCOREPAIR CRM material to the prepared surface using a trowel or a gloved hand. Manual working - Use the product to apply a scratch coat. Thickness should be 5 – 25 mm in single layer. If required higher thickness not more than 50 mm, the second layer applied while the first is still wet.

5. Consumption

Approximately 2.5 – 3.5 m^2 / 30 Kg bag at 5 - 8 mm thickness

6. Curing

It is a very important to prevent early plastic state moisture loss prior to the product setting. Cured product thoroughly after it has set by keeping it wet and covered for at least 7 days or apply a curing compound.

7. Tools & Clean Up

Compulsory Mixing with twin-shaft mixer. If using a mixing pump, use a batch mixer. Clean tools with soapy water while the material is still fresh.

8. Coverage

Approximately 25 - 35 ft^2 / 30 KG bag @ 5 - 8mm thickness

9. Packaging

Available in 30 Kg and 50 Kg sealed bag.

10. Shelf Life

6 months from the date of production if stored in original, unopened packaging & in places protected from moisture, sun exposure and frost.

11. Disposal

Larger quantities of leftover product should be disposed of in the original containers in accordance with the applicable regulations. Completely empty, clean containers should be recycled. Do not dispose of together with household waste. Do not allow to enter the sewage system. Do not empty into drains.

DISCLAIMER:

While the technical details & recommendations contained in this document and the related details given by the representatives of the company correspond to the best of our knowledge & experience, all the above information must in any case be considered as merely indicative and subject to confirmation. Users are recommended to conduct a product suitability test before it is used at full scale. In any case, the consumer alone is entirely liable for any consequences resulting from using the product. For the most up-to-date TDS, please visit our website at www.ascolite.in. Our company policy is one of ongoing R&D; therefore, we reserve the right to update this information without prior notice at any time. As the correct identification of the problems, the quality of other materials used, on-site environmental conditions and the workmanship on-site are factors beyond our control, there is no express or implied guarantee/ warranty as to the results achieved. The company assumes no liability or consequential damage arising from the use of our products for unsatisfactory results. Site visits are not a supervisory responsibility wherever provided. Suggestions made either verbally or in writing by the company may be followed, modified or rejected by the owner, engineer or contractor, since they are solely responsible for carrying out procedures appropriate to a specific application.